


RIP-RAP STONE OF A SIZE SPECIFIED BY THE PROJECT ENGINEER



- NOTES:**
1. THICKNESS AND TYPE OF GEOTEXTILE TO BE DETERMINED BY A LICENSED ENGINEER.
 2. SIZE AND GRADATION OF RIP-RAP TO BE DETERMINED BY A LICENSED ENGINEER.
 3. EDGES OF THE GEOTEXTILE SHALL EXTEND FROM BOTTOM OF ANCHOR TRENCH TO BOTTOM OF ANCHOR TRENCH.
 4. OVERLAP GEOTEXTILE PANELS A MINIMUM OF 12" (307.8 MM) AT LAP JOINTS.
 5. GEOTEXTILE SHALL BE COVERED IN ACCORDNACE WITH MANUFACTURER'S RECOMMENDATIONS.
 6. GEOMEMBRANE AND LINER ARE INTERCHANGEABLE TERMS.

Firestone

20 Geomembranes that Work 09

FP-R Geomembrane

Rip-rap Detail

Detail No. ML-R-1

Systems Polypropylene